BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/01/2019-20 Dated: 25-4-2019

APPROVED TENDER SCHEDULE –'B'

Item-06

Name of Work:-Construction of Sumudaya Bhavana at Someshwaranagara near Eshwara temple in ward no:04

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri A KUMAR REDDY	
				Rate	Rate In Words
1	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2018-19	cum	65.10	360.00	Rupees Three Hundred Sixty Only
2	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No 17.1) SR 2018-19	cum	65.10	75.00	Rupees Seventy Five Only
3	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2018-19	Cum	5.40	5300.00	Rupees Five Thousand Three Hundred Only
4	KSRB 5.2.3 Providing and constructing granite / trap / basalt rubble stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 Page No. 23/ Item No. 5.6/ PWD SR 2018-19	Cum	7.68	4700.00	Rupees Four Thousand Seven Hundred Only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri A KUMAR REDDY	
				Rate	Rate in Words
5	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 26/ Item No. 5.9/ PWD SR 2018-19	Cum	5.76	5800.00	Rupees Five Thousand Eight Hundred Only
6	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 112/ Item No. 15.1 PWD SR 2018-19	sqm	12.80	140.00	Rupees One Hundred Forty Only
7	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms, in depth, compacting each deposited layers by ramming after watering with lead upto 50m, and lift upto 1.5m, including cost of all labour complete as per specifications, specification. No. KBS 2.9, No. 6/ Item No. 2.10/ PWD SR 2018-19	Cum	24.00	180.00	Rupees One Hundred Eighty Only
8	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed 2008 machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.6, No. 13/ Item No. 4.11/ PWD SR 2018-19	Cum	57.38	5600.00	Rupees Five Thousand Six Hundred Only
9	KSRB 4-6.5 : Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 17/ Item No. 4.32/ PWD SR 2018-19	sqm	162.67	444.00	Rupees Four Hundred Forty Four Only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri A KUMAR REDDY	
				Rate	Rate in Words
10	KSRB 4-6.10 : Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels etc., including edges including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 16/ Item No. 4.37/ PWD SR 2018-19	sqm	7.20	330.00	Rupees Three Hundred Thirty Only
11	KSRB 4-6.3 : - Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thicknesss above 200mm including cost of all materials, labour complete as per specification KSRB Page No. 17/ Item No. 4.30/ PWD SR 2018-19	Sqm	78.00	415.00	Rupees Four Hundred Fifteen Only
12	KSRB 4-6.7 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1 m in depth including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 17/ Item No. 4.34/ PWD SR 2018-19	sqm	111.90	290.00	Rupees Two Hundred Ninety Only
13	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. Page No. 25/ Item No. 5.27/ PWD SR 2018-19	sqm	121.80	940.00	Rupees Nine Hundred Forty Only
14	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 Page No. 17/ Item No. 4.46/ PWD SR 2018-19	Tonne	5.74	74500.00	Rupees Seventy Four Thousand Five Hundred Only
15	KSRB 15.3.1 : Providing 12mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever reuired smooth rendering, : Providing and removing scaffolding, including cost of materials, labour. Curing complete as per specifications. Page No. 122/ Item No. 15.11/ PWD SR 2018-19	sqm	365.87	180.00	Rupees One Hundred Eighty Only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri A KUMAR REDDY	
				Rate	Rate In Words
16	KSRRB M800-20: Tubular steel railing of medium weight steel channel (ISMC series) 100 mm x 50 mm :- providing, fixing and erecting 50 mm dia steel pipe railing in 3 rows duly painted on medium weight steel channels (ISMC series) 100 mm x 50 mm, 1.2 meter high above ground, 2m center to center, complete as per approved drawings as per specifications, MORTH specifications No. 808, No. Page No 186 Item no 24.24 SR 2018-19	Mtr	12.00	1500.00	Rupees One Thousand Five Hundred Only
17	KSRB 9.4-2: Providing Honne wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps) but including cost of materials. Page No 51 Item no 9.11 SR 2018-19	Cum	0.50	94000.00	Rupees Ninety Four Thousand Only
18	KSRB 9.7.1: Providing and fixing in position fully panelled Honne wood shutters for doors styles and rails of 30mm. Thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of material 9.34 Page No 51 item no 9.21 SR 2018-19	Sqm	4.20	4500.00	Rupees Four Thousand Five Hundred Only
19	KSRB 9.21.2: Providing and fixing in position half panelled Honne wood shutters for window&ventilatorsstyles and rails of 20mm. Thick with bottom and lock rails 75mm wide top rail and styles 100mm wide as per drawing and panels of 20mm thick including cost of materials labours and complete as per specification Item no 9.65 Page No 56 SR 2018-19	Sqm	21.60	4180.00	Rupees Four Thousand One Hundred Eighty Only
20	FIXTURES for doors and windows Page No XIV SR 2018-19 VENTILATORS Sl No 395,385,402,386 Hinges 5" heavyduty	Each	4.00	37.00	Rupees Thirty Seven Only
	bottom lock nail	Each	10.00	47.00	Rupees Forty Seven Only
	MS Clamps	Each	8.00	35.00	Rupees Thirty Five Only
	Brass screws 25mm	Each	50.00	2.00	Rupees Two Only
21	KSRB 7.9: Providing and fixing M.S. Grill work for windows and ventilators weighing 21kg/sqm using M.S Flats or M.S. Square roads, or combination of M.S. flats and quare roads as per approved design drawing including cutting steel sections and welding the same to required pattern with a cost of red lead primer, cost of materials fixtures labour and HOM of machinery complete as per specification Page No 32 Item No 7.9 SR 2018-19	Kgs	453.60	100.00	Rupees One Hundred Only
22	KSRB15-7 : Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing complete as per specifications. (P.99/15.33) SR 2018-19	Sqm	162.31	32.00	Rupees Thirty Two Only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri A KUMAR REDDY	
				Rate	Rate in Words
23	KSRB 8.6-8: Providing and fixing on wall surface 4.0Kg/Sqcm HDPE rain down water pipes 110mm outer dia. Approved makes and brand with necessary specials like shoes, bends and offsets fixed with iron clamps, wall plugs, screws, including cost of materials, page No 47 item no 8.19 SR 2018-19	Rmtr	16.00	540.00	Rupees Five Hundred Forty Only
24	KSRB 15-14.1: Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after throughly brooming the surface free from mortar drops and other foreign matter Page No 117 item no 15.49 SR 2018-19	Sqm	340.07	90.00	Rupees Ninety Only
25	KSRB 15-17.1 : Applying priming coat over new wood surface and / or wood based surface with white lead paint priming including preparing the surface after thoroughly cleaning oil, grease, dirt, and foreign matter, sand papering and knotting ready mix paint including cost of materials, labour, complete as per specifications. Page No. 118 Item no 15.55 SR 2018-19	Sqm	30.00	40.0	Rupees Forty Only
26	KSRB 15-17.6: Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications. Page No.119 / Item No. 15.60.1 / PWD SR 2018-19	Sqm	30.00	90.00	Rupees Ninety Only
27	KSRB 10-2: Providing and laying integral cement based waterproofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc, consisting of following application. (a) Applying and grouting a slurry coat of neat cement using 2.75kg/sqm conforming admixed with proprietary water proofing compound conforming to IS:2645 over the RCC slab after cleaning the surface before treatment, (b) laying cement concrete using broken brick bats 25mm to 100mm size with 50% of cement mortar 1:5 admixed with proprietary water proofing compound conforming IS:2645 over 20mm thick layer of cement layer of cement mortar 1:5 admixed with proprietary water proofing compound to required slope and treating similarly the adjoining walls upto 300mm height including rounding off junction of walls and slabs, (c) after two days of proper curing, applying a second coat of cement lurry admixed with proprietary water proofing compound (d) Finishing the surface with 20mm thick jointless cement mortar of mix 1:4 admixed with proprietary water proofing compound and finally finishing the surface with trowel and neat cement slurry and making of 3000x300mm square, (e) the	sqm	60.00	900.00	Rupees Nine Hundred Only

Sl	Description	Unit	Approved Qty	Approved Rates Srl A KUMAR REDDY	
				Rate	Rate In Words
28	Providing and fixing 40mm thick sadarhalli grey flamed granite slab for bath areas in Bathrooms over a bed of 25mm thick CM 1:6 and fixing granite slab with CM: 1:3 . Page No. 116/ Item No. 15.57 / PWD SR 2018-19	sqm	57.50	1680.00	Rupees One Thousand Six Hundred Eighty Only
29	pointing wiring using copper with switch: Supplying and wiring adoping loop system in exiting PVC conduit/casing caping using copper PVC insulated multi strand 2 x1.5 sqmm coper wire with a 6 Amps flush type SP control switch shall be fixed on the existing plastic sheet/gang box, the other end of wires shall be terminated with sufficient loose length in a wood/PVC round block. Complete for each outlet.II point wiring using class B materials (3/6) a) Short point upto 3 mtrs from tapping point to out let via switch	Each	1.00	160.00	Rupees One Hundred Sixty Only
30	Medium point above 3Mtrs upto 6Mtrs from taping point to out let via switch	Each	1.00	245.00	Rupees Two Hundred Forty Five Only
31	a) Long point above 6Mtrs upto 10 Mtrs from tapping point to out let via switch	Each	1.00	340.00	Rupees Three Hundred Forty Only
32	Wiring for lightin/power circuit using one of PVC insulted 1100v grade,multistrand copper conductor single core cable in open or consealed system of wiring.II Group B e) 6 sqmm (9/20)	Each	1.00	40.00	Rupees Forty Only
33	Groove Cutting : Supplying ... dia 2mm/2.5mm thick heavy gauage PVC Conduit Pipe with bends metal junction boxes adhesive paste etc., and bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out the conduit wherever necessary a) 19/20mm dia 2mm thick (2/3)	Per Mtr	1.00	40.00	Rupees Forty Only
34	Supplying and fixing PVC/metal conduit accessories special type Junction Box a) 19/20mm junction box (3/5)	Each	1.00	15.00	Rupees Fifteen Only
35	DEEP Junction Box a) 18/20 mm deep junction box	Each	1.00	29.00	Rupees Twenty Nine Only
36	32.Supplying and fixing metal fan box with round hook (32/11)	Each	1.00	70.00	Rupees Seventy Only
37	Supplying and flush mounting teak wooden box with out front plank made of not less than 12mm thick wood after due groove cutting necessary masonry patch work complete. (6/3) b) 12"x9"x3" (300x228x76mm)	Each	1.00	80.00	Rupees Eighty Only
38	Supplying and fixing of modular switch/Scocket/stepped electronic fan regulator/dimmer/telephone socket etc on existing modular switch plate. II using group B" Meterial (8/18) e) 600 watts dimmer	Each	1.00	390.00	Rupees Three Hundred Ninety Only
39	g) 16 Amps one way switch	Each	1.00	110.00	Rupees One Hundred Ten Only
40	J) 6/16 Amps Universal Socket	Each	1.00	170.00	Rupees One Hundred Seventy Only

Sl	Description	Unit	Approved Qty	Approved Rates Sri A KUMAR REDDY	
				Rate	Rate In Words
41	Supplying 4mm thick plastic sheet with necessary nitches for fixing switches regulators etc., and fixing on existing wooden or metal box using N.F.Screws. (22/10)	sq.cm	20.00	0.22	Rupees and Paise Twenty Two Only
42	Supply patty type fluorescent tube light fitting of 4-36/40 watts flourescent tube fitting,made out of M.S sheet and stove eanmeled with low loss open construction copper wound ferromagnetic ballast, strter,locking type prass contact holders mounted on double fold type sheet base fully wired for use on 230 volts A C supply including 1NO 4-36/40 watts fluorescent tube.) (2/16) Group A	Each	1.00	350.00	Rupees Three Hundred Fifty Only
43	Fixing all types and all capacities fluorescent/false celing/spot light/CFL fitting indoor on the wall/ celing/rafters/griders using 23/0.0076" twin twisted PVC insulated wires,required nos of blocks and clamps(if required) a) On wall/ ceiling/ Rafter/Griders (7/29)	Each	2.00	100.00	Rupees One Hundred Only
44	Fixing one ceiling/wall mounting fan of all capacities and all types to the exiting S hook with fan regular to the exiting board together with supplying and fixing a 5 ampers ceiling rose,necessary langth of 23/0.0076 inch PVC insulated twin twisted copper wire and wiring completely. (8/29)	Each	1.00	100.00	Rupees One Hundred Only
45	Fixing one exhaust fan in the nitch already left in the wall with bolts and nuts 5 amps ceiling rose with sufficient length of 23/0.0076 inch PVC insulated twin core wire of apporoved Make (12/29)	Each	1.00	310.00	Rupees Three Hundred Ten Only
46	Supplying,fixing wiring earth electrode for grouding conduits. I.C cutouts and other equipment on the meter board using 40mm dia 2.90 thick GI2.5 mtrlong buried in a pit should be filled with equal proporation of salt and charcoal 150mm alround the pipe to complete depth. The conection from the pipe to the conduit etc is to be established throughGI wire of size as oer ISI specifications 7.33 of IS 732 using 12mm dia bolts,nuts,washers and checknutsetc,the pipe shall have 16 through holes 12mm dia (68/01)	Each	2.00	1900.00	Rupees One Thousand Nine Hundred Only
47	suplying and mixing miniature circuit breakers on exiting MCB distribution boards using necessary fixing materials and C type curve,indicator ON/OFF energy cross-3 with short circuit breaking capacity of 10k and complete wiring as required. a) 32 Amps SP 1)Group A (12/36)	Each	3.00	170.00	Rupees One Hundred Seventy Only

Sl	Description	Unit	Approved Qty	Approved Rates Sri A KUMAR REDDY	
				Rate	Rate in Words
48	Energy meter box. Supply and instalation/fixing/ provision of outdoor type thermoplastic modular panel enclousers with transperent polycarbonate lid shock proof,coreosion proof having internally embedded gasket on both lid and flap suitable to fix. Single phase/three phase energy meter in suitable base plate and having a provision fo fuse/ MCB cutout with suitable transperent hinged flap opening for operating MCB along with complete tamper proof SEALING facility. a) 300 x 300 x 214 mm (40/42)	Each	3.00	2200.00	Rupees Two Thousand Two Hundred Only
49	Supplying of LT UG cable having aluminium conductor PVC insulated,sheathed,galvanized,steel wire/steel tap armoured cable with PVC outer sheathing 1.1KV class A PVC Cabled)4 core 16 sqmm (68/04)	Per Mtr	3.00	100.00	Rupees One Hundred Only
50	Labour charges for laying of 1.1KV Class UG cable in existing trench GI pipe stoneware pipe/on wall/on pole as required a) 6sqmm to 16 10 sqmm (5/69)	Mtr	3.00	5.00	Rupees Five Only
51	Digging of trench of 0.6mm deep * 0.50 mtr wide refilling the trench to the required ground level and consolidating etc. complete.(As per Civil SR KSRB 1-2p-7)a. in Ordinary soil (6/70)	Mtr	3.00	30.00	Rupees Thirty Only
52	Supplying and fixing of class A (medium duty) GI pipe of wall thick ness not lessthan 3.25mm on pole/wall/drain crossing eith necessary clamping arrangements for UG cable of 1.1 KV class B.50 mm (9/70)	Mtr	3.00	200.00	Rupees Two Hundred Only
53	Suplying and fixing L.T cast Iron Pot Heads suitable for 1.1KV class UG cable filled with Necessary bitumen/insulating compound complete with erminals,clamps,bolts,nuts and washers etc,. b. 16 Sqmm (10/70)	Each	3.00	200.00	Rupees Two Hundred Only
54	KSRB 13-8.11 Providing and fixing to wall, ceiling and floor, low-density polyethylene pipes 10.00KGf/sq.cm. working pressure 25mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling an floor including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No. 13.2.15.1 / 13.9,, Page No. 103/ Item No. 13.76 / PWD SR 2018-19	Mtrs	20.00	100.00	Rupees One Hundred Only

Sl	Description	Unit	Approved Qty	Approved Rates Sri A KUMAR REDDY	
				Rate	Rate In Words
55	KSRB 13.11.1: Providing and placing on terrace. Polyethylene water storage tanks with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications. (For 1000 litre capacity) Specification NO. KBS 13.22 Page No. 94 Item no 13.78 SR 2018-19	Each	1.00	7000.00	Rupees Seven Thousand Only
56	KSRB 13-6 5.1: Providing and fixing in position 15mm nominal bore brass ferrule with C.I. mouth cover including boring and tapping the main, cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specifications NO KBS 13.3.3 / 13.14 Page No. 89// Item No. 13.43 / PWD SR 2018-19	Each	4.00	150.00	Rupees One Hundred Fifty Only
57	KSRB 11-3: Providing and fixing white vitreous china clay, water closet Indian type (Squatting pan) of size 580m with footrests, 100 mm S or P trap, (approved make) cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11 Page No. 77/ Item No. 12.3 PWD SR 2018-19	Each	3.00	1350.00	Rupees One Thousand Three Hundred Fifty Only

A. K S Reddy
Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.